

File No.	Island	Street Address	City	ZIP Code	TMK	Applicant (as appropriate)	Exempt. HAR 11-200.1-15(c)	Action: Title & Description	Notes
STP-1500(126)	Maui		Wailuku	96793	(2) 3-8-007:999	Hawaii DOT	Type 1, Part 1, B.3 Type 3, Part 1.1 Type 3, Part 1.4 Type 3, Part 2.3 Type 3, Part 2.5	Title: KAAHUMANU AVENUE SIDEWALK GAPS MAUI LANI PARKWAY TO MAHALANI STREET Description: The proposed project includes installing curb, gutter, and sidewalk improvements on the south side of Kaahumanu Avenue, between milepost 0.92 and milepost 1.11 (+/-1,005 feet). The proposed sidewalk improvements will connect to the existing sidewalks east and west of the project area and is listed as a top priority for the island of Maui in the Statewide Pedestrian Master Plan, dated May 2013. The existing guardrail system will be removed, and new guardrails and end treatments will be installed to meet current standards. Minor asphalt concrete paving improvements will also be constructed to facilitate the installation of a new curb and gutter, within the shoulder area, and a new guardrail system, behind the new sidewalk. The attached project location map illustrates the general location of the project area. All construction will occur within the HDOT ROW. No staging area is planned or anticipated for materials or equipment storage within the project area. The estimated start of construction is September 2024, with a completion time of 160 working days. Night work is not anticipated.	
377A-01-22M	Maui		Kula	96790	(2) 2-3-022:067 (2) 2-3-999:999	Hawaii DOT	Type 1, Part 1.A.4a Type 1, Part 1.A.4b Type 1, Part 1.B.3 Type 2, Part 1 B.3 Type 2, Part 1 B.8 Type 3, Part 1.14 Type 3, Part 2.3 Type 8, Part 1.8.g	Title: HALEAKALA HIGHWAY SLOPE AND SHOULDER REPAIR VICINITY OF AINAKULA ROAD TO KULALANI DRIVE Description: The project scope includes reconstructing the eroded slope area and repaving the southbound travel lane and shoulder. In addition, curb and gutter, a concrete drainage chute, a grouted rubble paving apron, permanent slope protection and new guardrail will be installed.	